



**NOTES:**

1. POLY PIPE SHALL BE 2" PE3408 HDPE POLY TUBING, ASTM D-2737 FOR 200 PSI WITH PERMANENT SPECIFICATION MARKINGS. TUBING FITTINGS SHALL REQUIRE STAINLESS STEEL INSERTS.
2. CONCRETE COLLAR MAY NOT BE REQUIRED IN PAVED AREAS IF PAVEMENT SURFACE IS FINISHED PRIOR TO CONDITIONAL FINAL INSPECTION AND VALVE BOX LID IS AT FINISHED GRADE.
3. TRAFFIC RATED BOXES SHALL BE REQUIRED IN ALL PAVED AREAS AND AREAS TO BE PAVED IN THE FUTURE.
4. ALL MATERIAL SHALL BE APPROVED BY THE TOWN OF JUPITER WATER UTILITIES PRIOR TO INSTALLATION.
5. ALL PIPING SHALL BE RESTRAINED PER TOWN OF JUPITER STANDARDS.
6. WHEN VALVE IS DEEPER THAN 36" AN EXTENSION WILL BE REQUIRED TO BRING OPERATING NUT TO +/- 24" OF FINISHED GRADE. EXTENSION MUST BE SET SCREW TYPE AND ATTACHED TO OPERATING NUT.
7. TRACER WIRE SHALL BE INSTALLED ON ALL NON-DUCTILE IRON WATER MAIN. SEE NOTE 3 ON W-06, TYPICAL UNDERGROUND VALVE INSTALLATION FOR TEST STATION AND TRACER WIRE MATERIAL.

**AUTOMATIC FLUSHING DEVICE**

**JUPITER UTILITIES**  
CONSTRUCTION STANDARDS AND DETAILS

DATE APPROVED:  
06/2017  
DRAWING No. W-19