



NOTES:

- A. THE CONTRACTOR SHALL START RESTORATION WORK IMMEDIATELY AFTER A MAXIMUM OF 500 LF OF UTILITY LINE IS INSTALLED. THE CONTRACTOR SHALL WATER SOD UNTIL A FIRM ROOT SYSTEM IS ESTABLISHED (MINIMUM 3 TIMES PER WEEK FOR 21 DAYS).
- B. UTILITY TRENCH SHALL NOT UNDERMINE SIDEWALK, DRIVEWAY, OR ROADWAY PAVEMENT. IF SUCH UNDERMINING OCCURS, THE UNDERMINED INFRASTRUCTURE SHALL BE REMOVED AND REPLACED IN ACCORDANCE WITH APPLICABLE TOJ ENGINEERING DIVISION STANDARD DETAILS, UNLESS APPROVED OTHERWISE BY THE TOWN ENGINEER.
- C. SEE STANDARD DETAIL 114a FOR ADDITIONAL REQUIREMENTS RELATED TO SHOULDER-SWALE RESTORATION.



TOWN OF JUPITER
ENGINEERING DIVISION
 210 MILITARY TRAIL
 JUPITER, FLORIDA 33458
 (561) 746-5134

UTILITY TRENCH
SHOULDER RESTORATION
 DETAIL AND REQUIREMENTS

V:\Engineering\Drawings\Details\2025\114 - Util Trench Restoration.dwg

DETAIL NUMBER

114

Revised 20230403