



NOTES:

1. ALL BACKFILL WILL REQUIRE COMPACTION TO SPECIFIED DENSITY, WITH DENSITY TESTS FOR ALL LIFTS (12" MAXIMUM LIFT).
2. SAW CUT ASPHALT BEFORE EXCAVATING AND AS REQUIRED PRIOR TO NEW ASPHALT PLACEMENT.
3. ASPHALT SHALL BE ROLLED/COMPACTED TO A SMOOTH UNIFORM SURFACE, LEVEL WITH EXISTING/ADJOINING ASPHALT.
4. MINIMUM ASPHALT DENSITY SHALL BE 94% OF MAXIMUM DESIGN DENSITY FOR ASPHALT MIX.



TOWN OF JUPITER
ENGINEERING DIVISION
 210 MILITARY TRAIL
 JUPITER, FLORIDA 33458
 (561) 746-5134

UTILITY TRENCH
PAVEMENT RESTORATION
 DETAIL AND REQUIREMENTS

V:\Engineering\Drawings\Details\2025\119 - Pavrest.dwg

DETAIL NUMBER

119

Revised 20220203