



- NOTES:
1. SAWCUTS REQUIRED AT 10' CENTERS WITHIN 48 HOURS OF POUR FOR ALL CURB TYPES.
  2. ALL CONCRETE STANDARD MIX - MIN. 3000 PSI IN 28 DAYS
  3. REFER TO FDOT INDEX 300.
  4. 12" DEPTH SUBGRADE COMPACTION TO 98% MAX DENSITY PER AASHTO T-180.



**TOWN OF JUPITER**  
**ENGINEERING DIVISION**  
 210 MILITARY TRAIL  
 JUPITER, FLORIDA 33458  
 (561) 746-5134

**COLLECTOR ROADWAY**  
**SAFETY EDGE**  
 DETAILS & SPECIFICATIONS

DETAIL NUMBER

**126**

Revised 20100820