



- NOTES:
1. SAWCUTS REQUIRED AT 10' CENTERS WITHIN 48 HOURS OF POUR FOR ALL CURB TYPES.
 2. ALL CONCRETE STANDARD MIX - MIN. 3000 PSI IN 28 DAYS
 3. REFER TO FDOT INDEX 300.
 4. 12" DEPTH SUBGRADE COMPACTION TO 98% MAX DENSITY PER AASHTO T-180.



TOWN OF JUPITER
ENGINEERING DIVISION
 210 MILITARY TRAIL
 JUPITER, FLORIDA 33458
 (561) 746-5134

COLLECTOR ROADWAY
SAFETY EDGE
 DETAILS & SPECIFICATIONS

DETAIL NUMBER
126
 Revised 20100820